Norm Pipe Clamps&Fixing Elements Industry&Trading Ltd.Co.			TENSILE TEST REPORT		Date:13.08.2013 Page: 1/1
TYPE	SIZE	SAMPLE NO	LOAD VALUE AT FRACTURE MENTIONED IN THE CATALOGUEİ( kN)	LOAD VALUE AT FRACTURE OBSERVED BY THE TEST ( kN)	DEFORMATION TYPE
NAKC 015	1/2"	1	10	11,135	Head's part was broken from clam
NAKC 015	1/2"	2	10	14,485	Pipe clamp was broken
NAKC 015	1/2"	3	10	13,780	Pipe clamp was broken
NASC 020	3/4"	1	10	14,020	Pipe clamp was broken
NASC 020	3/4"	2	10	13,800	Pipe clamp was broken
NASC 020	3/4"	3	10	13,695	Pipe clamp was broken
NAKC 025	1"	1	10	14,255	Pipe clamp was broken
NAKC 025	1"	2	10	14,410	Pipe clamp was broken
NAKC 025	1"	3	10	14,275	Pipe clamp was broken
NASC 032	1 1/4"	1	10	13,985	Pipe clamp was broken
NASC 032	1 1/4"	2	10	13,115	Pipe clamp was broken
NASC 032	1 1/4"	3	10	14,055	Pipe clamp was broken
NAKC 040	1 1/2"	1	10	14,100	Pipe clamp was broken
NAKC 040	1 1/2"	2	10	13,925	Pipe clamp was broken
NAKC 040	1 1/2"	3	10	14,730	Pipe clamp was broken
NASC 050	2"	1	10	13,570	Pipe clamp was broken
NASC 050	2"	2	10	13,180	Pipe clamp was broken
NASC 050	2"	3	10	13,800	Pipe clamp was broken
NAKC 065	2 1/2"	1	10	12,690	Pipe clamp was broken
NAKC 065	2 1/2"	2	<del>10</del> ~	12,480	Pipe clamp was broken
NAKC 065	2 1/2"	3	10	13,375	Pipe clamp was broken
NASC 080	3"	1	10	11,220	Pipe clamp was broken
NASC 080	3"	2	10	11,635	Pipe clamp was broken
NASC 080	3"	3	10	12,115	Pipe clamp was broken
NAKC 100	4"	1	14	20,165	Pipe clamp was broken
NAKC 100	4"	2	14	22,005	Pipe clamp was broken
NAKC 100	4"	3	14	21,890	Pipe clamp was broken
NASC 125	5"	1	20	22,155	Side Screw was broken
NASC 125	5"	2	20	22,285	Pipe clamp was broken
NASC 125	5"	3	20	20,960	Nut was broken from clamp
NAKC 150	6"	1	20	25,140	Clamp head was broken
NAKC 150	6"	2	20	29,165	Pipe clamp was broken
NAKC 150	6"	3	20	23,530	Pipe clamp was broken

Signature:

Signature: